

CLASS E: EARTHWORKS**LABOUR RESOURCES**

The following Labour rates are based upon the Construction Industry Council agreement on pay dated 25 June 2007 and the current Working Rule Agreement.

	Hourly rate £
General operative unskilled	12.94
Skilled operative rate 4	13.74
Skilled operative rate 3	14.69
Skilled operative rate 2	15.77
Skilled operative rate 1	16.94
Craft operative	17.98

	Hourly rate £	Total rate £	Gang rate £
ELA Cuttings gang			
1 x unskilled	12.94	12.94	
1 x rate 2	15.77	15.77	
1 x rate 3	14.69	<u>14.69</u>	43.40
ELB Foundations gang			
1 x unskilled	12.94	12.51	
1 x rate 3	14.69	14.69	
1 x rate 4	13.74	<u>13.74</u>	40.94
ELC General excavation gang			
1 x unskilled	12.94	12.94	
1 x rate 3	14.69	14.69	
1 x rate 4	13.74	<u>13.74</u>	41.37
ELD Trimming/preparation gang			
1 x unskilled	12.94	12.94	
1 x rate 3	14.69	<u>14.69</u>	27.63
ELE Filling gang			
1 x unskilled	12.94	12.94	
1 x rate 3	14.69	14.69	
1 x rate 4	13.74	<u>13.74</u>	41.37

ELF Geotextile gang

1 x unskilled	12.94	12.94	
1 x rate 4	13.74	<u>13.74</u>	26.68

ELG Onsite loading gang

1 x unskilled	12.94	12.94	
2 x rate 3	14.69	<u>29.38</u>	42.32

ELH Offsite loading gang

1 x unskilled	12.94	12.94	
2 x rate 3	14.69	<u>28.38</u>	41.32

ELI Landscaping gang

1 x unskilled	12.51	12.51	
1 x rate 4	14.69	<u>14.69</u>	27.20

PLANT RESOURCES

Hourly rate £	Gang rate £
---------------------	-------------------

The rates in this section are based upon plant hired from a specialist plant hire firm. The rates exclude the cost of fuel VAT, delivery, servicing and repairs.

EPA General excavation gang

1 x backactor (21 tonne)	<u>33.65</u>	33.65
--------------------------	--------------	-------

EPB Breaking gang

1 x backactor (21 tonne)	33.65	
1 x breaker (1000kg)	<u>9.84</u>	43.49

EPC Trimming/preparation gang

1 x grader	<u>38.54</u>	38.54
------------	--------------	-------

EPD Filling gang

1 x tractor loader	20.69	
1 x vibrating roller	<u>11.73</u>	32.42

EPE Geotextile gang

1 x tractor loader	<u>20.69</u>	20.69
--------------------	--------------	-------

EPF Onsite loading gang

1 x 25t dump truck	38.22	
1 x backactor (21 tonne)	<u>33.65</u>	71.87