

	Unit	Plant gang	Net Plant £	Labour gang	Net Labour £	Net mat'ls £	Net total £	O'heads & profit £
Excavate for foundations in unreinforced concrete not exposed at the Commencing Surface								
not exceeding 0.25m	m3	EPB 0.35	15.22	ELB 0.35	14.33	0.00	29.55	4.43
0.25-0.5m	m3	EPB 0.40	17.40	ELB 0.40	16.38	0.00	33.77	5.07
0.5-1m	m3	EPB 0.50	21.75	ELB 0.50	20.47	0.00	42.22	6.33
1-2m	m3	EPB 0.55	23.92	ELB 0.55	22.52	0.00	46.44	6.97
Excavate for foundations in reinforced concrete not exposed at the Commencing Surface								
not exceeding 0.25m	m3	EPB 0.50	21.75	ELB 0.50	20.47	0.00	42.22	6.33
0.25-0.5m	m3	EPB 0.55	23.92	ELB 0.55	22.52	0.00	46.44	6.97
0.5-1m	m3	EPB 0.70	30.44	ELB 0.70	28.66	0.00	59.10	8.87
1-2m	m3	EPB 0.80	34.79	ELB 0.80	32.75	0.00	67.54	10.13
<b>General excavation</b>								
General excavation for topsoil								
0.25-0.5m	m3	EPA 0.03	1.01	ELC 0.03	1.24	0.00	2.25	0.34
0.5-1m	m3	EPA 0.03	1.01	ELC 0.03	1.24	0.00	2.25	0.34
General excavation in materials other than topsoil, rock or other hard material								
0.25-0.5m	m3	EPA 0.04	1.35	ELC 0.04	1.65	0.00	3.00	0.45
0.5-1m	m3	EPA 0.04	1.35	ELC 0.04	1.65	0.00	3.00	0.45
1-2m	m3	EPA 0.06	2.02	ELC 0.06	2.48	0.00	4.50	0.68

	<b>Unit</b>	<b>Plant gang hours</b>	<b>Net Plant £</b>	<b>Labour gang hours</b>	<b>Net Labour £</b>	<b>Net mat'ls £</b>	<b>Net total £</b>	<b>O'heads &amp; profit £</b>
2-5m	m3	EPA 0.08	2.69	ELC 0.08	3.31	0.00	6.00	0.90
5-10m	m3	EPA 0.15	5.05	ELC 0.15	6.21	0.00	11.25	1.69
10-15m	m3	EPA 0.21	7.07	ELC 0.21	8.69	0.00	15.75	2.36
General excavation in rock								
0.25-0.5m	m3	EPB 0.25	10.87	ELC 0.25	10.34	0.00	21.22	3.18
0.25-0.5m	m3	EPB 0.30	13.05	ELC 0.30	12.41	0.00	25.46	3.82
0.5-1m	m3	EPB 0.40	17.40	ELC 0.40	16.55	0.00	33.94	5.09
1-2m	m3	EPB 0.50	21.75	ELC 0.50	20.69	0.00	42.43	6.36
2-5m	m3	EPB 0.60	26.09	ELC 0.60	24.82	0.00	50.92	7.64
General excavation in in unreinforced concrete exposed at the Commencing Surface								
not exceeding 0.25m	m3	EPB 0.30	13.05	ELC 0.30	12.41	0.00	25.46	3.82
0.25-0.5m	m3	EPB 0.35	15.22	ELC 0.35	14.48	0.00	29.70	4.46
0.5-1m	m3	EPB 0.45	19.57	ELC 0.45	18.62	0.00	38.19	5.73
1-2m	m3	EPB 0.50	21.75	ELC 0.50	20.69	0.00	42.43	6.36
General excavation in in reinforced concrete exposed at the Commencing Surface								
not exceeding 0.25m	m3	EPB 0.45	19.57	ELC 0.45	18.62	0.00	38.19	5.73
0.25-0.5m	m3	EPB 0.50	21.75	ELC 0.50	20.69	0.00	42.43	6.36

	Unit	Plant gang	Net Plant £	Labour gang	Net Labour £	Net mat'ls £	Net total £	O'heads & profit £
0.5-1m	m3	EPB 0.65	28.27	ELC 0.65	26.89	0.00	55.16	8.27
1-2m	m3	EPB 0.75	32.62	ELC 0.75	31.03	0.00	63.65	9.55
General excavation in in unreinforced concrete not exposed at the Commencing Surface								
not exceeding 0.25m	m3	EPB 0.35	15.22	ELC 0.35	14.48	0.00	29.70	4.46
0.25-0.5m	m3	EPB 0.40	17.40	ELC 0.40	16.55	0.00	33.94	5.09
0.5-1m	m3	EPB 0.50	21.75	ELC 0.50	20.69	0.00	42.43	6.36
1-2m	m3	EPB 0.55	23.92	ELC 0.55	22.75	0.00	46.67	7.00
General excavation in in reinforced concrete not exposed at the Commencing Surface								
not exceeding 0.25m	m3	EPB 0.50	21.75	ELC 0.50	20.69	0.00	42.43	6.36
0.25-0.5m	m3	EPB 0.55	23.92	ELC 0.55	22.75	0.00	46.67	7.00
0.5-1m	m3	EPB 0.70	30.44	ELC 0.70	28.96	0.00	59.40	8.91
1-2m	m3	EPB 0.80	34.79	ELC 0.80	33.10	0.00	67.89	10.18
<b>Excavation ancillaries</b>								
Trimming of excavated surfaces								
topsoil								
horizontal	m2	EPC 0.01	0.39	ELD 0.01	0.28	0.00	0.66	0.10
inclined 10 to 45 degrees to the horizontal	m2	EPC 0.02	0.77	ELD 0.02	0.55	0.00	1.32	0.20