

	Unit	Plant gang hours	Net Plant £	Labour gang hours	Net Labour £	Net mat'ls £	Net total £	O'heads & profit £
Geotextiles								
Filter membrane, LAid on excavated or filled surfaces to receive Granular material								
Terram 500	m2	EPE 0.02	0.41	ELF 0.02	0.53	0.41	1.36	0.20
Terram 700	m2	EPE 0.02	0.41	ELF 0.02	0.53	0.44	1.39	0.21
Terram 1000	m2	EPE 0.02	0.41	ELF 0.02	0.53	0.48	1.43	0.21
Terram 2000	m2	EPE 0.02	0.41	ELF 0.02	0.53	1.03	1.98	0.30
Polypropylene SS20 Geogrid	m2	EPE 0.03	0.62	ELF 0.03	0.80	1.76	3.18	0.48
Polypropylene SS30 Geogrid	m2	EPE 0.03	0.62	ELF 0.03	0.80	2.61	4.03	0.60
Polypropylene SS40 Geogrid	m2	EPE 0.04	0.83	ELF 0.04	1.07	4.16	6.05	0.91
Landscaping								
Turfing								
Lay imported turf on prepared bed								
meadow turf	m2			ELG 0.08	3.39	1.32	4.71	0.71
sports turf	m2			ELG 0.08	3.39	1.83	5.22	0.78
domestic lawn	m2			ELG 0.08	3.39	1.96	5.35	0.80
Grass seeding by hand seed cost £60/25kg								
10g per m2	m2	EPH 0.01	0.07	ELI 0.01	0.27	0.02	0.36	0.05
20g per m2	m2	EPH 0.01	0.07	ELI 0.01	0.27	0.04	0.38	0.06
30g per m2	m2	EPH 0.02	0.14	ELI 0.02	0.54	0.06	0.75	0.11