

	<b>Unit</b>	<b>Plant gang hours</b>	<b>Net plant £</b>	<b>Labour gang hours</b>	<b>Net labour £</b>	<b>Net mat'ls £</b>	<b>Net total £</b>	<b>O'heads &amp; profit £</b>
<b>Concrete pipes</b>								
Concrete pipes, Class L, with flexible joints, nominal bore								
300mm								
depth, not exceeding 1.5m	m	IPB 0.30	10.20	ILA 0.30	21.69	13.41	45.30	6.80
depth, 1.5 - 2m	m	IPB 0.32	10.88	ILA 0.32	23.14	13.41	47.43	7.11
depth, 2 - 2.5m	m	IPB 0.34	11.56	0.34	24.58	13.41	49.55	7.43
depth, 2.5 - 3m	m	IPB 0.38	12.92	ILA 0.38	27.47	13.41	53.80	8.07
depth, 3 - 3.5m	m	IPB 0.46	15.64	ILA 0.46	33.26	13.41	62.31	9.35
depth, 3.5 - 4m	m	IPB 0.56	19.04	ILA 0.56	40.49	13.41	72.94	10.94
375mm								
depth, not exceeding 1.5m	m	IPB 0.32	10.88	ILA 0.32	23.14	17.10	51.12	7.67
depth, 1.5 - 2m	m	IPB 0.34	11.56	0.34	24.58	17.10	53.24	7.99
depth, 2 - 2.5m	m	IPB 0.36	12.24	0.36	26.03	17.10	55.37	8.31
depth, 2.5 - 3m	m	IPB 0.40	13.60	0.40	28.92	17.10	59.62	8.94
depth, 3 - 3.5m	m	IPB 0.48	16.32	0.48	34.70	17.10	68.12	10.22
depth, 3.5 - 4m	m	IPB 0.58	19.72	0.58	41.93	17.10	78.75	11.81
450mm								
depth, not exceeding 1.5m	m	IPB 0.34	11.56	0.34	24.58	19.90	56.04	8.41
depth, 1.5 - 2m	m	IPB 0.36	12.24	0.36	26.03	19.90	58.17	8.73
depth, 2 - 2.5m	m	IPB 0.38	12.92	0.38	27.47	19.90	60.29	9.04

	<b>Unit</b>	<b>Plant gang hours</b>	<b>Net plant £</b>	<b>Labour gang hours</b>	<b>Net labour £</b>	<b>Net mat'ls £</b>	<b>Net total £</b>	<b>O'heads &amp; profit £</b>
Concrete pipes, 450mm bore (cont'd)								
depth, 2.5 - 3m	m	IPB 0.42	14.28	ILA 0.42	30.37	19.90	64.55	9.68
depth, 3 - 3.5m	m	IPB 0.50	17.00	ILA 0.50	36.15	19.90	73.05	10.96
depth, 3.5 - 4m	m	IPB 0.60	20.40	ILA 0.60	43.38	19.90	83.68	12.55
525mm								
depth, not exceeding 1.5m	m	IPB 0.32	10.88	ILA 0.32	23.14	24.70	58.72	8.81
depth, 1.5 - 2m	m	IPB 0.36	12.24	ILA 0.36	26.03	24.70	62.97	9.45
depth, 2 - 2.5m	m	IPB 0.40	13.60	ILA 0.40	28.92	24.70	67.22	10.08
depth, 2.5 - 3m	m	IPB 0.44	14.96	ILA 0.44	31.81	24.70	71.47	10.72
depth, 3 - 3.5m	m	IPB 0.48	16.32	ILA 0.48	34.70	24.70	75.72	11.36
depth, 3.5 - 4m	m	IPB 0.52	17.68	ILA 0.52	37.60	24.70	79.98	12.00
600mm								
depth, not exceeding 1.5m	m	IPC 0.34	25.84	ILB 0.34	29.25	30.10	59.35	8.90
depth, 1.5 - 2m	m	IPC 0.38	28.88	ILB 0.38	32.70	30.10	91.68	13.75
depth, 2 - 2.5m	m	IPC 0.42	31.92	ILB 0.42	36.14	30.10	98.16	14.72
depth, 2.5 - 3m	m	IPC 0.46	34.96	ILB 0.46	39.58	30.10	104.64	15.70
depth, 3 - 3.5m	m	IPC 0.50	38.00	ILB 0.50	43.02	30.10	111.12	16.67
depth, 3.5 - 4m	m	IPC 0.54	41.04	ILB 0.54	46.46	30.10	117.60	17.64
675mm								
depth, not exceeding 1.5m	m	IPC 0.35	26.60	ILB 0.35	30.11	47.30	77.41	11.61
depth, 1.5 - 2m	m	IPC 0.39	29.64	ILB 0.39	33.56	47.30	110.50	16.57

	<b>Unit</b>	<b>Plant gang hours</b>	<b>Net plant £</b>	<b>Labour gang hours</b>	<b>Net labour £</b>	<b>Net mat'ls £</b>	<b>Net total £</b>	<b>O'heads &amp; profit £</b>
Concrete pipes, 675mm bore (cont'd)								
depth, 2 - 2.5m	m	IPC 0.43	32.68	ILB 0.43	37.00	47.30	116.98	17.55
depth, 2.5 - 3m	m	IPC 0.47	35.72	ILB 0.47	40.44	47.30	123.46	18.52
depth, 3 - 3.5m	m	IPC 0.51	38.76	ILB 0.51	43.88	47.30	129.94	19.49
depth, 3.5 - 4m	m	IPC 0.55	41.80	ILB 0.55	47.32	47.30	136.42	20.46
750mm								
depth, not exceeding 1.5m	m	IPC 0.36	27.36	ILB 0.36	30.97	54.60	112.93	16.94
depth, 1.5 - 2m	m	IPC 0.40	30.40	ILB 0.40	34.42	54.60	119.42	17.91
depth, 2 - 2.5m	m	IPC 0.44	33.44	ILB 0.44	37.86	54.60	125.90	18.88
depth, 2.5 - 3m	m	IPC 0.48	36.48	ILB 0.48	41.30	54.60	132.38	19.86
depth, 3 - 3.5m	m	IPC 0.52	39.52	ILB 0.52	44.74	54.60	138.86	20.83
depth, 3.5 - 4m	m	IPC 0.56	42.56	ILB 0.56	48.18	54.60	145.34	21.80
825mm								
depth, not exceeding 1.5m	m	IPC 0.38	28.88	ILB 0.38	32.70	66.70	128.28	19.24
depth, 1.5 - 2m	m	IPC 0.42	31.92	ILB 0.42	36.14	66.70	134.76	20.21
depth, 2 - 2.5m	m	IPC 0.46	34.96	ILB 0.46	39.58	66.70	141.24	21.19
depth, 2.5 - 3m	m	IPC 0.50	38.00	ILB 0.50	43.02	66.70	147.72	22.16
depth, 3 - 3.5m	m	IPC 0.54	41.04	ILB 0.54	46.46	66.70	154.20	23.13
depth, 3.5 - 4m	m	IPC 0.58	44.08	ILB 0.58	49.90	66.70	160.68	24.10

	<b>Unit</b>	<b>Plant gang hours</b>	<b>Net plant £</b>	<b>Labour gang hours</b>	<b>Net labour £</b>	<b>Net mat'ls £</b>	<b>Net total £</b>	<b>O'heads &amp; profit £</b>
Concrete pipes(cont'd)								
900mm								
depth, not exceeding 1.5m	m	IPC 0.40	30.40	ILB 0.40	34.42	77.10	141.92	21.29
depth, 1.5 - 2m	m	IPC 0.44	33.44	ILB 0.44	37.86	77.10	148.40	22.26
depth, 2 - 2.5m	m	IPC 0.48	36.48	ILB 0.48	41.30	77.10	154.88	23.23
depth, 2.5 - 3m	m	IPC 0.52	39.52	ILB 0.52	44.74	77.10	161.36	24.20
depth, 3 - 3.5m	m	IPC 0.56	42.56	ILB 0.56	48.18	77.10	167.84	25.18
depth, 3.5 - 4m	m	IPC 0.60	45.60	ILB 0.60	51.62	77.10	174.32	26.15
1050mm								
depth, not exceeding 1.5m	m	IPC 0.42	31.92	ILB 0.42	36.14	96.40	164.46	24.67
depth, 1.5 - 2m	m	IPC 0.46	34.96	ILB 0.46	39.58	96.40	170.94	25.64
depth, 2 - 2.5m	m	IPC 0.50	38.00	ILB 0.50	43.02	96.40	177.42	26.61
depth, 2.5 - 3m	m	IPC 0.54	41.04	ILB 0.54	46.46	96.40	183.90	27.59
depth, 3 - 3.5m	m	IPC 0.58	44.08	ILB 0.58	49.90	96.40	190.38	28.56
depth, 3.5 - 4m	m	IPC 0.62	47.12	ILB 0.62	53.34	96.40	196.86	29.53
1200mm								
depth, not exceeding 1.5m	m	IPC 0.44	33.44	ILB 0.44	37.86	124.30	195.60	29.34
depth, 1.5 - 2m	m	IPC 0.48	36.48	ILB 0.48	41.30	124.30	202.08	30.31
depth, 2 - 2.5m	m	IPC 0.52	39.52	ILB 0.52	44.74	124.30	208.56	31.28
depth, 2.5 - 3m	m	IPC 0.56	42.56	ILB 0.56	48.18	124.30	215.04	32.26
depth, 3 - 3.5m	m	IPC 0.60	45.60	ILB 0.60	51.62	124.30	221.52	33.23

	<b>Unit</b>	<b>Plant gang hours</b>	<b>Net plant £</b>	<b>Labour gang hours</b>	<b>Net labour £</b>	<b>Net mat'ls £</b>	<b>Net total £</b>	<b>O'heads &amp; profit £</b>
Concrete pipes, 1200mm bore (cont'd)								
depth, 3.5 - 4m	m	IPC 0.64	48.64	ILB 0.64	55.07	124.30	228.01	34.20
1350mm								
depth, not exceeding 1.5m	m	IPC 0.46	34.96	ILB 0.46	39.58	188.40	262.94	39.44
depth, 1.5 - 2m	m	IPC 0.50	38.00	ILB 0.50	43.02	188.40	269.42	40.41
depth, 2 - 2.5m	m	IPC 0.54	41.04	ILB 0.54	46.46	188.40	275.90	41.39
depth, 2.5 - 3m	m	IPC 0.58	44.08	ILB 0.58	49.90	188.40	282.38	42.36
depth, 3 - 3.5m	m	IPC 0.62	47.12	ILB 0.62	53.34	188.40	288.86	43.33
depth, 3.5 - 4m	m	IPC 0.66	50.16	ILB 0.66	56.79	188.40	295.35	44.30
1500mm								
depth, not exceeding 1.5m	m	IPC 0.48	36.48	ILB 0.48	41.30	272.30	350.08	52.51
depth, 1.5 - 2m	m	IPC 0.52	39.52	ILB 0.52	44.74	272.30	356.56	53.48
depth, 2 - 2.5m	m	IPC 0.56	42.56	ILB 0.56	48.18	272.30	363.04	54.46
depth, 2.5 - 3m	m	IPC 0.60	45.60	ILB 0.60	51.62	272.30	369.52	55.43
depth, 3 - 3.5m	m	IPC 0.64	48.64	ILB 0.64	55.07	272.30	376.01	56.40
depth, 3.5 - 4m	m	IPC 0.68	51.68	ILB 0.68	58.51	272.30	382.49	57.37
1800mm								
depth, not exceeding 1.5m	m	IPC 0.50	38.00	ILB 0.50	43.02	306.20	387.22	58.08
depth, 1.5 - 2m	m	IPC 0.54	41.04	ILB 0.54	46.46	306.20	393.70	59.06
depth, 2 - 2.5m	m	IPC 0.58	44.08	ILB 0.58	49.90	306.20	400.18	60.03
depth, 2.5 - 3m	m	IPC 0.62	47.12	ILB 0.62	53.34	306.20	406.66	61.00

	<b>Unit</b>	<b>Plant gang hours</b>	<b>Net plant £</b>	<b>Labour gang hours</b>	<b>Net labour £</b>	<b>Net mat'ls £</b>	<b>Net total £</b>	<b>O'heads &amp; profit £</b>
Concrete pipes, 1800mm bore (cont'd)								
depth, 3 - 3.5m	m	IPC 0.66	50.16	ILB 0.66	56.79	306.20	413.15	61.97
depth, 3.5 - 4m	m	IPC 0.70	53.20	ILB 0.70	60.23	306.20	419.63	62.94
2100mm								
depth, not exceeding 1.5m	m	IPC 0.52	39.52	ILB 0.52	44.74	518.70	602.96	90.44
depth, 1.5 - 2m	m	IPC 0.56	42.56	ILB 0.56	48.18	518.70	609.44	91.42
depth, 2 - 2.5m	m	IPC 0.60	45.60	ILB 0.60	51.62	518.70	615.92	92.39
depth, 2.5 - 3m	m	IPC 0.64	48.64	ILB 0.64	55.07	518.70	622.41	93.36
depth, 3 - 3.5m	m	IPC 0.68	51.68	ILB 0.68	58.51	518.70	628.89	94.33
depth, 3.5 - 4m	m	IPC 0.72	54.72	ILB 0.72	61.95	518.70	635.37	95.31
2400mm								
depth, not exceeding 1.5m	m	IPC 0.54	41.04	ILB 0.54	46.46	692.30	779.80	116.97
depth, 1.5 - 2m	m	IPC 0.58	44.08	ILB 0.58	49.90	692.30	786.28	117.94
depth, 2 - 2.5m	m	IPC 0.62	47.12	ILB 0.62	53.34	692.30	792.76	118.91
depth, 2.5 - 3m	m	IPC 0.66	50.16	ILB 0.66	56.79	692.30	799.25	119.89
depth, 3 - 3.5m	m	IPC 0.70	53.20	ILB 0.70	60.23	692.30	805.73	120.86
depth, 3.5 - 4m	m	IPC 0.74	56.24	ILB 0.74	63.67	692.30	812.21	121.83